ENGINEERING DEPARTMENT.

KOLAR DIVISION.

Abstract Notification, dated 19th December 1932.

The attention of the public is invited to the notification published in pages 1490 and 1491 of the *Mysore Gazette*, dated 22nd December 1932, calling for tenders for the work of Restoring Byraganahalli Breached Minor Tank, Registered No. 53 of Sidlaghatta Taluk.

The last date fixed for the receipt of tender is Monday the 23rd January 1933 before 2 P.M.

Abstract Notification dated 19th December 1932.

The attention of the public is invited to the notification published in pages 1491 and 1492 of the *Mysore Gazette*, dated 22nd December 1932, calling for tenders for the work of Restoring Alipore Balikunte Tank, Registered No. 88 of Goribidnur Taluk.

The last date fixed for receipt of tenders is 23rd January 1933, 2 P.M.

C. T. NARASIMHA IYENGAR,
Executive Engineer,

TUMKUR DIVISION.

Abstract Notification dated 10th December 1932.

Subject:—Construction of a Rural Dispensary Building at Urudagere in the Tumkur Taluk.

Attention of the public is drawn to notification calling for tenders for the above work in pages 1467 and 1468 of Part VI of *Mysore Gazette*, dated 15th December 1932.

(2) The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, upto 3 P.M., of 10th January 1933.

(3) An earnest money of Rs. 250 should accompany the tender.

Abstract Notification, dated 16th December 1932.

Subject:—Opening a feeder channel to Yekarahalli Tank in Madhugiri Taluk.

Attention of the public is drawn to notification calling for tenders for the above work in pages 1480 to 1482, Part VI of the *Mysore Gazette*, dated 22nd December 1932.

2. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 3 P.M., of 25th January 1933.

3. An earnest money of Rs. 700 should accompany the tender.

A. TANDONI RAO,
Executive Engineer.

KADUR DIVISION.

Dated 28th December 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 16th January 1933, till 3 P.M., for making good the damages to Garji Anicut for the year 1932-33. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. to 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred and forty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for making good the damages to Garji Anicut for the year 1932-33", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. Rates should be quoted for each and every item.

10. Percentage quotations either below the lowest tender or below the estimated rates will not be accepted.

11. In all matters of dispute regarding quality of work or rates, the decision of the Superintending Engineer is final and legally binding.

12. No claims for enhanced rates should be preferred after the acceptance of tender or at any time during the execution of work.

13. For lumpsum items and also items found necessary during execution, rates as per current Schedule rates or at tendered rates for such of the items as form a portion in lumpsum provision or as per data worked out and approved by Superintending Engineer will be allowed.

14. No representations regarding rates, etc., from the rejected tenderers will be considered.

15. The contractor shall hold himself responsible for the good behaviour of his employees of all gardes.

Approximate estimated quantities for making good the damages to Garji Anicut for 1932-33.

No.	Items	Per	Quantity	Rate to be quoted	
				In figures	In words
1	Dismantling brick in mortar ...	C.ft.	428		
2	Benching rock for construction ..	S.ft.	385		
3	Concrete in surki mortar ...	C.ft.	193		
4	Rubble masonry in surki mortar including grouting of surki mortar.	,,	2,380		
5	Setting the old stone slabs in surki mortar including cement pointing, conveying from the river bed.	S.ft.	52		
6	Surki concrete coping mixed with cement	C.ft.	88		
7	Surki mortar plastering mixed with cement.	Sqr.	2·10		
8	Pointing with surki mortar mixed with cement.	,,	5·25		
9	Dismantling stone in surki mortar ...	C.ft.	488		
10	Earthwork excavation for foundation in slush mixed with jelly boulders.	C.yd.	227		
11	Concrete stone jelly in surki mortar ...	C.ft.	2,133		
12	Rubble masonry in surki mortar including grouting of surki mortar.	,,	7,435		
13	Clearing and removing debris such as sand, etc., for scours.	C.yd.	127		
14	Old jelly filling including collecting scattered jelly in the river bed from a distance of 200 feet.	,,	476		
15	Surki mortar concrete mixed with cement.	C.ft.	5,940		
16	Cement plastering ..	Sqr.	49·65		
17	Fixing old burnt stone slabs in surki mortar and cement pointing.	S.ft.	40		
18	Providing and fixing new burnt stone slabs 6" thick in surki motar and cement pointing.	,,	30		
19	Cement pointing ...	Sqr.	4·35		
20	Removing the top existing apron beyond the wall C. D. for seating of new apron.	C.yd.	889		
21	Collecting, carting and dumping new jelly to scour, etc.	,,	1,141		
22	Rough stone apron (old) by collecting scattered stones from the bed.	,,	·444		
23	New stone apron with big stones with jelly wedging, etc., complete.	,,	444		
24	Grouting apron with surki concrete and cement rendering at top complete.	Sqr.	114		
25	Putting ring bund ...	Lump	sum		

Dated 28th December 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 16th January 1933, till 3 P.M., for making good the damages to Thangli Anicut for 1932-33.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chickmagalur between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred and ten only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for making good the damages to Thangli Anicut" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each and every item.

10. Percentage quotations either below the lowest tender or below the estimated rates will not be accepted.

11. In all matters of dispute regarding quality of work or rates, the decision of the Superintending Engineer is final and legally binding.

12. No claims for enhanced rates should be preferred after the acceptance of tender or at any time during the execution of work.

13. For lump sum items and also items found necessary during execution, rates as per current scheduled rates or as per data struck will be allowed.

14. No representations regarding rates, etc., from the rejected tenderers will be considered after the acceptance of tender.

15. The contractor will be held responsible for the good behaviour of his employees of all grades.

Approximate abstract showing quantities for repairing the damages done by floods to Thangli Anicut, Kadur Taluk.

No	Details of work	Unit	Quantity	Rates	
				In figures	In words
	ANICUT.				
1	Earthwork excavation for foundation in slush mixed with jelly boulders, etc:	C.yds.	210		
2	Concrete stone jelly in surki mortar ..	C.ft.	1,604		
3	Rubble masonry in surki mortar with surki grouting mortor.	,,	5,075		
4	Coping with surki concrete mixed with cement.	,,	434		
5	Surki mortor mixed with cement plastering over coping	Sqr.	8·67		
6	Dismantling the loose apron ...	C.yds.	141		
7	Old jelly fillng including collecting scattered jelly in the river bed.	Cyd.	190		
8	Collecting carting and dumping new jelly, (big size) to scours.	,,	190		
9	Rough stone apron (old) by collecting stacked stones from the river bed.	,,	192		
10	New stone apron with big stones, jelly wedging, etc., complete.	,,	191		
11	Grouting apron with surki concrete and cement rendering at top concrete.	Sqr.	172·64		
12	Putting ring bund, etc. ...	Lump	sum		

CHITALDRUG DIVISION.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 20th January 1933, for constructing the Muslim Hostel at Devangere, Chitaldrug District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed within the time fixed in the agreement.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 530 in cash or Government promissory notes as earnest money and be superscribed "Tender for Constructing the Muslim Hostel at Davangere" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The quotation that the work will be done at certain percentage less or more than the estimate will not be accepted.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates in the tender should be noted in figures as well as in words and there should be no corrections.

Abstract quantities of Estimate for Constructing a Muslim Hostel at Davangere, Chitaldrug District.

No.	Items of work	Unit	Quantity
1	Earthwork excavation	Cyd.	99
2	Stone jelly concrete	Cft.	921
3	Burnt stone in mud	,,	2434
4	Burnt brick in mud	,,	3010
5	Do mortar	,,	556
6	Burnt stone slabs 6" thick	Sft.	697
7	Providing cut stone pillars 7' high 8" square with base and capital, etc., complete.	Each	10
8	Teak wood door with pannelled shutters, hinges, etc., complete	Sft	123
9	Do windows with half pannelled and half glazed shutters with iron bars, etc., complete.	,,	189
10	Teak wood ventilators with glazed shutters with iron bars, etc., complete.	,,	84
11	Teak wood wall shelves with frames, planks and panelled shutters etc., complete.	,,	149
12	Teak wood wrought and put up with wood oiling. ...	Cft.	118·88
13	Rolled steel joists with painting and including hoisting, etc. ...	Cwt.	54

No.	Items of work	Unit	Quantity
14	Providing iron fixtures for joists	Lump	sum
15	Jack arch terrace	Sqr.	6·23
16	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete.	,,	19·91
17	Providing parapet wall 1½' high with plastering, etc., complete	R.ft.	101
18	Cornice	,,	328
19	Flooring with 1st class Mangalore tiles on 3" concrete bed with cement pointing, etc., complete.	Sqr.	11·31
20	Flooring with Kadappa slabs on 3" concrete bed with cement pointing, etc.	,,	6·04
21	Chunam plastering, nice	,,	70·62
22	White washing, 2 coats	,,	70·62
23	Cement pointing to basement	,,	4·78
24	Cudappah slab wall plates	,,	1·00
25	Ridge tile set in mortar	R.ft.	89
26	Teakwood finials	Each	2
27	Chunam borders	R.ft.	105
28	Silicate painting	Sqr.	7·91
29	Unforeseen items	Lump	sum
	Constructing an Out house for Muslim Hostel at Davangere.		
1	Earthwork excavation	C.yd.	54
2	Stone jelly concrete	C.ft.	493
3	Stone in mud	..	1,361
4	Brick in mud	...	1,327
5	Burnt brick in mortar	...	413
6	Burnt stone slabs 6" thick roughly dressed and fixed ...	,,	242
7	Providing cut stone pillars 7' high 8" square with base and capital, etc., complete.	Each	3
8	Teakwood doors battened with iron clamp, etc., complete ...	S.ft.	113
9	Teakwood windows with battened shutters with iron bars, etc., complete.	,,	158
10	Teakwood ventilators with glazed shutters with iron bars, etc., complete.	S.ft.	9
11	Teakwood work wrought and put up with wood oiling ..	C.ft.	31·80
12	Rolled steel joists with painting, hoisting, etc., complete ...	Cwt.	20·1
13	Providing iron fixtures to joists, ...	Lump	sum
14	Providing Cudappah slab for wall plates	Sqr.	0·75
15	Jack arch terrace	,,	2·86
16	Roofing with 1st class Mangalore tiles on teak-reepers ...	,,	6·45
17	Ridge tiles set in mortar	R.ft.	43
18	Parapet wall with brick in mortar 1½' high with plastering, etc., complete.	,,	81
19	Cornice	,,	203
20	Chunam plastering	Sqr.	36·94
21	White washing	,,	36·94
22	Flooring with 1st class Mangalore tiles on 3" concrete bed with cement pointing.	,,	5·40
23	Do do Cudappah slabs	,,	1·00
24	Painting with silicate	,,	5·58
25	Constructing sinks and drains	Lump	sum
26	Providing smoke tiles	Each	4
27	Do pestle and mortar	,,	1
28	Do stone benches for keeping things in store room ...	Lump	sum
1	Constructing a latrine for the above Hostel	Lump	sum

R TIPPAIYA,
Executive Engineer.